



- GENERAL NOTES:**
- Allow for 2mm high impact edging, matching Melawood finish, to all exposed sides and ends
 - Joins in Melawood countertops to be biscuit jointed (or similar) and glued. No cover strips allowed
 - All internal shelving to be height adjustable, unless indicated otherwise.
 - Hinges:** Allow a minimum of 2x hinges per door below counter top height and minimum of 4x hinges per door for full height doors (to underside of ceiling). Hinges to be 100° opening and with soft closing feature, fixed onto cupboard carcass and inside of door face, with accessories, all installed as per manufacturer's specifications.
 - Drawer Runners: N/A
 - Handles: N/A
 - Locks:** Blum CABLOXX locking system to all drawers and cupboards, with accessories, all installed as per manufacturer's specifications.
 - Management Holes:** To be cut and fitted post installation with input from end-user. Cutting and installation at as per manufacturer's specifications.


- MATERIALS AND FINISHES:**
- Kickplate: SA Pine based to all cupboard carcasses – with PG Bison - colour: 'Kaleplana' Peen finish to all visible faces
 - Cupboard Carcass: Melawood - colour: 'Iceberg White' (Peen finish)
 - Door Fronts: High pressure PVC laminate finish to MDF - colour: Glass White. Sample to be provided for approval by Architect
 - Drawer Fronts: High pressure PVC laminate finish to MDF - colour: Glass White. Sample to be provided for approval by Architect
 - Countertop/Worktop: EzeiQuartz - colour: 'Blanco Cloud'
 - Worktop: EzeiQuartz - colour: 'Iceberg White'




Plan
1 : 25




Elevation Front
1 : 25




Elevation Right
1 : 25



Section A
1 : 10



Elevation Back
1 : 25



Section B
1 : 10

- General Notes**
- The design on this drawing is copyright and remains the property of SVA International (Pty) Ltd. Reg. No 2011/137280/07
 - All work to be carried out in strict accordance with local authority requirements, National Building Regulations, and the S.A.S.S. standards.
 - This drawing may not be scaled. Only figured dimensions and levels may be used.
 - All relevant details, levels, and dimensions must be checked on site before commencement of work. Any discrepancies to be reported to the Architects office immediately

Revisions			
Rev	Date	Issued by	Description
1	2025.11.05		Issued for Costing

Key Plan

Consultants

Project Manager Mr Bubele Dyantyi	043 704 7138
Quantity Surveyor Excel Quantity Surveyors - Ntombodidi Ndumane	081 592 1681
Structural Engineer PCI - Jacques Van Zyl	041 450 4989
Civil Engineer PCI - Jacques Van Zyl	041 450 4989
Mechanical Engineer CA Du Toit - Andries Strauss	041 585 7559
Electrical Engineer CA Du Toit - Andries Stauss	041 585 7559

Wet & Fire Services Engineer

Interior Designer

Landscape Architect

Lighting Specialist

Client
University of Fort Hare - Alice Campus

Project
UFH - Alice Campus Finance Offices Conversion

Project Location
University of Fort Hare - Alice Campus

Drawing
JT01 - Security Desk

Scale	Size	Project No.	Revision No.
As indicated	A1	P25002-00	
Drawing No. A-(74)6001	Date 2025.11.05	Revision No. 1	

Issued for:

COSTING



1st Floor St Georges Corner, 116 Park Drive, Central, Port Elizabeth, 6001

SVA INTERNATIONAL (PTY) LTD
Member of the GIBB GROUP of companies
CapeTown | Durban | Johannesburg | Lagos | Maputo | Mauritius | Port Elizabeth